



RUSTIC PLANK SPECIFICATION SHEET

Artefact Collection Engineered T&G plank by Forté. 15mm thick, 220mm wide, 1800-2200mm length. Direct stick installation method onto substrate. Rustic grade, reactive stain, pre-finished with Bona® Matte Lacquer

PRODUCT DETAILS

Collection	Artefact
Product Type	Engineered Plank
Availability	Stocked
Total Thickness	15mm
Width	220mm
Length	1800-2200mm
% of Shorts	Up to 33%
Wear Layer	4mm Solid European Oak
Core	Birch Plywood
Construction	2-layer Engineered
Re-sands	Up to 2 (approx. 1mm removed per re-sand)
Surface Texture	Brushed
Surface Sheen	Matte
Bevel	Bevel 4 sides (1.2mm all sides)
Status	Pre-finished (no additional coats required)
Finish	Reactive stain with Bona® Matte Lacquer (6 coats)
Species	European Oak
Wood Grade	Rustic (refer page 2 for details)
Filler Colour	Dependant on colour, visit forte.co.nz for accurate filler colour

The Artefact Collection is also available in herringbone pattern with stair nosings to match.

WARRANTY

10 Year Commercial	For terms and conditions see
25 Year Residential	www.forte.co.nz/warranties

SUSTAINABILITY

FSC® Certified | Low VOC
No added Formaldehyde



Ammonite

Amulet

Flint

Obsidian

INSTALLATION

Installation Method	Glue down (Double Stick for Multi-level)
Suitable Substrates	Plywood, Particle Board, Concrete, existing timber - enquire for others
Joint Profile	Tongue and Groove (4 sides)
Suitable Applications	Flooring, Walls, Ceilings
Suitable Uses	Residential homes, hospitality, retail stores, restaurants, apartments
Underfloor Heating	• Hydronic Systems • Electric Systems set in screed (ensure screed suitable for UFH) - enquire for others
Wet Area Suitability	Contact the Forté team for information 0508 35 66 77

TECHNICAL SPECIFICATIONS

Reaction to Fire (Floors)	Awaiting test results
Reaction to Fire (Walls and Ceilings)	Awaiting test results
<u>Formaldehyde Emission</u>	
AS/NZS 2098.11	E1 (0.03mg/L)
Wear Layer Density	650-700kg/m ³
<u>Slip Ratings</u>	
AS/NZS 4586 Wet Test	Classification F, Mean COF 0.55
AS/NZS 4586 Dry Test	Classification X, Pendulum Mean 42 SRV

PACK INFORMATION

<u>Pack 1</u>	<u>1800mm Lengths</u>
Pack Size / Weight	2.376m ² / 28.6kg
Pieces Per Pack	4 full planks + up to 2 split planks
<u>Pack 2</u>	<u>2000mm Lengths</u>
Pack Size / Weight	2.64m ² / 31.8kg
Pieces Per Pack	4 full planks + up to 2 split planks
<u>Pack 3</u>	<u>2200mm Lengths</u>
Pack Size / Weight	2.904m ² / 35kg
Pieces Per Pack	4 full planks + up to 2 split planks

Plank Profile

ARTEFACT PLANK

Image Coming Soon

ARTEFACT – RUSTIC GRADE



An Artefact Rustic grade plank will contain natural colour and structural variation. This grade allows for more frequent, extreme knots and sapwood and discolouration will be expected throughout the planks. Patched knots and cracks will be present and are finished with filler dependent on the products colour.

Care and Maintenance

RESIDENTIAL AND COMMERCIAL CARE AND MAINTENANCE

Forté's Product Specialists have collated our care and maintenance recommendations to ensure your flooring looks like new for years to come. Residential and Commercial projects require different levels of care and maintenance. Visit www.forte.co.nz/careandmaintenance

Warranty

ARTEFACT 25 YEAR RESIDENTIAL WARRANTY

The Afterfact Collection comes with a full 25 year Residential Warranty. For full warranty terms and conditions, please visit www.forte.co.nz/warranties

ARTEFACT 10 YEAR COMMERCIAL WARRANTY

The Afterfact Collection comes with a full 10 year Commercial Warranty. For full warranty terms and conditions, please visit www.forte.co.nz/warranties

Installation

THE ARTEFACT COLLECTION MUST BE INSTALLED BY A TRAINED PROFESSIONAL

Please ensure that you have read and understood the installation guidelines before proceeding to install Afterfact timber flooring. If you have any questions or concerns, please call the Forté technical team on 0508 35 66 77. Failure to adhere to the Forté Installation Guidelines may void your warranty.

For full installation guidelines, please visit www.forte.co.nz/installation